

#### **Description**

The 5X2503 MicroClock is a programmable clock generator and is intended for low-power, consumer, wearable and smart devices.

The 5X2503 device is a 3 PLL architecture design. Each PLL is individually programmable, allowing for up to 3 unique frequency outputs. The 5X2503 has built-in unique features such as Proactive Power Saving (PPS) to deliver better system-level power management.

An internal OTP memory allows the user to store the configuration in the device without programming after power up. It can then be reprogrammed again through the  $I^2C$  interface.

The device has programmable VCO and PLL source selection allowing the user to do power-performance optimization based on the application requirements. A low-power 32.768kHz clock is supported with only less than  $2\mu A$  current consumption for system RTC reference clock needs.

# **Typical Applications**

- SmartDevice, Handheld, Wearable applications
- Consumer application crystal replacement

#### **Features**

- Configurable OE1 pin function as OE, PPS or DFC control function
- PPS: Proactive Power Saving features save power during the end device power-down mode
- DFC: Dynamic Frequency Control feature allows programming up to 4 difference frequencies that switch dynamically
- Integrated 26MHz crystal; no external input source requirement
- Spread spectrum clock support to lower system EMI
- I<sup>2</sup>C Interface


#### **Output Features**

- 3 LVCMOS outputs, 1MHz–125MHz
- Low-power 32.768kHz clock supported
- Wireless clock crystal integration and fan-out directly

#### **Key Specifications**

- 2μA operation for RTC clock 32.768kHz output
- 2.5 x 2.5 mm 12-DFN with crystal integration; small-form-factor package

#### **Block Diagram**





# **Power Group**

Power Supply	SE	DIV	MUX	PLL	DCO	Xtal
V <sub>DDOUT1</sub>	OUT1	_	_	_	_	_
V <sub>DDOUT2</sub>	OUT2/OUT3	_	_	V	_	_
V <sub>DD1_8</sub>		V	V	_	V	V

# **Output Source Selection Register Setting Tables**

OUT3 Source	B35b7	B35b6
Divider 3 (DIV3)	0	0
Divider 5 (DIV5)	0	1
Divider 1 (DIV1)	1	0
32.768kHz DCO	1	1

OUT2 Source	B35b5	B35b4
Divider 3 (DIV3)	0	0
Divider 5 (DIV5)	0	1
Divider 1 (DIV1)	1	0
32.768kHz DCO	1	1


OUT2 Source	B35b3	B35b2
Divider 3 (DIV3)	0	0
Divider 5 (DIV5)	0	1
Divider 1 (DIV1)	1	0
32.768kHz DCO	1	1

DIV1 Source	B35b7	B35b6
PLL1	0	0
DIV4 seed	1	Х



#### **Pin Assignments**

Figure 1. Pin Assignments for 2.5 × 2.5 mm 12-DFN Package



2.5 × 2.5 mm 12-DFN

#### **Pin Descriptions**

**Table 1. Pin Descriptions** 

Number	Name	Туре	Description
1	SDA_DFC0/OE2	I/O	I <sup>2</sup> C data pin; can be DFC0 function by OTP programming or selected by SEL_DFC at power-on default. Output enable pin for OUT2.
2	SEL_DFC/SCL_DFC1/OE3	Input	I <sup>2</sup> C clock pin; can be DFC1 function by OTP programming selected by SEL_DFC at power-on default. Output enable pin for OUT3.
3	V <sub>SS</sub>	Power	Ground pin.
4	V <sub>SS</sub>	Power	Ground pin.
5	V <sub>DD1_8</sub>	Power	1.8V power rail.
6	V <sub>DDOUT1</sub>	Power	1.2V / 1.8V output clock power supply pin; supports OUT1.
7	OUT1	Output	1.2V / 1.8V LVCMOS clock output.
8	OE1	Input	Output enable control 1.
9	OUT2	Output	1.8V LVCMOS clock output.
10	V <sub>DDOUT2</sub>	Power	1.8V output clock power supply pin; supports OUT2/3.
11	OUT3	Output	1.8V LVCMOS clock output.
12	V <sub>SS</sub>	Power	Ground pin.
_	EPAD	GND	Connect to ground pad.


#### **Device Feature and Function**

#### **DFC - Dynamic Frequency Control**

- OTP programmable–4 different feedback fractional dividers (4 VCO frequencies) that apply to PLL2.
- ORT (overshoot reduction) function will be applied automatically during the VCO frequency change.
- Smooth frequency incremental or decremental from current VCO to targeted VCO base on DFC hardware pins selection.



Figure 2. DFC Function Block Diagram



**Table 2. DFC Function Priority** 

DFC Mode	OE Pins	DFC_EN bit (W32[4])	OE1_fun_sel	I <sup>2</sup> C Pins	SCL_DFC1	SDA_DFCO	DFC[1:0]	Notes
Off	OE In*	0	00 or 01 or 10*	Active (SCL = 1 at POR)	SCL Input	SDA I/O	N/A	DFC disable
On	DFC0 In	1	11	Active	SCL Input	SDA I/O	DFC0 = OE	One pin DFC via OE1
On	OE In*	1	00 or 01 or 10*	Inactive (SCL = 0 at POR)	DFC1	DFC0	DFC1 = SCL_DFC1	I <sup>2</sup> C pin as DFC control pins
On	OE In*	1	00 or 01 or 10*	Active (SCL = 1 at POR)	SCL Input	SDA I/O	W30[1:0]	I <sup>2</sup> C control DFC mode

<sup>\*</sup> See OE Pin Function table.

# **DFC Function Programming**

- Register B63b3:2 selects DFC00–DFC11 configuration.
- Byte16–19 are the registers for PLL2 VCO setting, based on B63b3:2 configuration selection, the data write to B16–19 will be stored in selected configuration OTP memory.
- Refer to *DFC Function Priority* table. Select proper control pin(s) to activate DFC function.
- Note the DFC function can also be controlled by I<sup>2</sup>C access.

#### **PPS - Proactive Power Saving Function**

PPS (Proactive Power Saving) is an IDT patented unique design for the clock generator that proactively detects end device power down state and then switches output clocks between normal operation clock frequency and low power mode 32kHz clock that only consumes < 5µA current. The system could save power when the device goes into power down or sleep mode. The PPS function diagram is shown as below.



Figure 3. PPS Function Block Diagram





Figure 4. PPS Assertion/Deassertion Timing Chart



#### **PPS Function Programming**

Refer to the *OE Pin Function* table to have proper PPS function selected for OE pin(s). Note that the register default is set to Output Enable (OE) function for OE pins.

# **Input Pin Function**

The input pins in 5X2503 have multiple functions. The OE1 pin can be configured as output enable control (OE) or chip power-down control (PD#) or Proactive Power Saving function (PPS). Furthermore, the OE1 pin can be configured as single or Dynamic Frequency Control (DFC).



SCL/SDA are also multiple function pins. The two pins can be configured as output enable control (OE), or I<sup>2</sup>C interface or Dynamic Frequency Control (DFC) functions by programming and hardware pin latch.

**Table 3. OE1 Pin Function Table** 

Function	Byte30		
Tunction	bit6	bit5	
OUT1 Output Enable/Disable	0	0	
Global Power Down (PD#)	0	1	
OUT1 Proactive Power Saving Input (OUT1 PPS)	1	0	
DFC0	1	1	

Table 4. SDA/SCL Function Selection

SEL_DFC (latched)	Enable OE2/3 B36<2>	DFC_EN B32<4>	OE1 Funsel B30<6:5>	Function of SCL/SDA
0	0	0	00, 01, 10	NA
0	0	1	00, 01, 10	SCL = DFC1, SDA = DFC0
0	1	X	00, 01, 10	SCL = OE3, SDA = OE2
1	X	X	00, 01, 10	SCL, SDA

### **Spread Spectrum**

The 5X2503 supports spread spectrum clocks from PLL1. PLL1 has built-in analog spread spectrum; PLL2 and PLL3 use seed clock from PLL1.

# **ORT - VCO Overshoot Reduction Technology**

The 5X2503 supports innovate the VCO overshoot reduction technology to prevent the output clock frequency spike when the device is change frequency on the fly or doing DFC (Dynamic Frequency Control) function.

The VCO frequency change are under control instead of free run to targeted frequency.

#### **PLL Features and Descriptions**

Table 5. Output Divider 1

Output Divider Bits [1:0]	Output Divider Bits [3:2]			
Output Divider Dits [1.0]	00	01	10	11
00	1	2	4	8
01	4	8	16	32
10	5	10	20	40
11	6	12	24	48



Table 6. Output Divider 2, 3, and 5


Output Divider Bits [1:0]	Output Divider Bits [3:2]				
Output Divider Dits [1.0]	00	01	10	11	
00	1	2	4	5	
01	3	6	12	15	
10	5	10	20	25	
11	10	20	40	50	

Table 7. Output Divider 4

Output Divider Bits [1:0]		Output Divid	der Bits [3:2]	
Output Divider Bits [1.0]	00	01	10	11
00	1	2	4	8
01	3	6	12	24
10	5	10	20	40
11	10	20	40	80

# **Output Clock Test Conditions**

Figure 5. LVCMOS Output Clock Test Condition



V <sub>DDO</sub>	R <sub>OUT</sub>	Rs
1.2V	30Ω	20Ω
1.8V	17Ω	33Ω



## **Absolute Maximum Ratings**

Stresses above the ratings listed below can cause permanent damage to the 5X2503. These ratings, which are standard values for IDT commercially rated parts, are stress ratings only. Functional operation of the device at these or any other conditions above those indicated in the operational sections of the specifications is not implied. Exposure to absolute maximum rating conditions for extended periods can affect product reliability. Electrical parameters are guaranteed only over the recommended operating temperature range.

**Table 8. Absolute Maximum Ratings** 

Item	Rating
Supply Voltage, V <sub>DD1_8</sub> , V <sub>DDOUTx</sub>	1.89V
Inputs	
Other Inputs	-0.5V to V <sub>DD1_8</sub> / V <sub>DDOUTx</sub>
Outputs, V <sub>DDOUTx</sub> (LVCMOS)	-0.5V to V <sub>DDOUTx</sub> + 0.5V
Outputs, IO (SDA)	10mA
Package Thermal Impedance, $\Theta_{JA}$	42°C/W (0mps)
Package Thermal Impedance, Θ <sub>JC</sub>	41.8°C/W (0mps)
Storage Temperature, T <sub>STG</sub>	-65°C to 150°C
ESD Human Body Model	2000V
Junction Temperature	125°C

# **Recommended Operating Conditions**

**Table 9. Recommended Operating Conditions** 

Symbol	Parameter	Minimum	Typical	Maximum	Units
V <sub>DDOUT1</sub>	Power Supply Voltage for Supporting OUT1	1.71	1.8	1.89	V
V <sub>DDOUT1</sub>	Power Supply Voltage for Supporting OUT1	1.14	1.2	1.26	V
V <sub>DDOUT2</sub>	/ <sub>DDOUT2</sub> Power Supply Voltage for Supporting OUT2/OUT3		1.8	1.89	V
V <sub>DD1_8</sub>	Power Supply Voltage for Core Logic Functions	1.71	1.8	1.89	V
T <sub>A</sub>	Ambient Operating Temperature	-40	_	85	°C
C <sub>LOAD_OUT</sub>	OAD_OUT Maximum Load Capacitance (1.8V LVCMOS only)		5	_	pF
t <sub>PU</sub>			_	3	ms



# Input Capacitance, LVCMOS Output Impedance, and Internal Pull-down Resistance ( $T_A$ = +25 °C)

Table 10. Input Capacitance, LVCMOS Output Impedance, and Internal Pull-down Resistance

Symbol	Parameter		Typical	Maximum	Units
C <sub>IN</sub>	Input Capacitance (OE, SDA, SCL)	_	3	7	pF
Pull-down Resistor	OE		150	_	kΩ
R <sub>OUT</sub>	LVCMOS Output Driver Impedance (V <sub>DDOUTx</sub> = 1.8V)	-	17	_	Ω

# **Integrated Crystal Characteristics**

**Table 11. Crystal Characteristics** 

Parameter	Test Conditions	Minimum	Typical	Maximum	Units
Mode of Oscillation	_		Fundamental		
Frequency	_	_	26	_	MHz
Frequency Tolerance (25°C) <sup>1</sup>	_	-20	_	20	ppm
Equivalent Series Resistance (ESR)	_	_	10	100	Ω
Shunt Capacitance	_	_	2	7	pF
Load Capacitance (C <sub>L</sub> )	_	6	8	10	pF
Maximum Crystal Drive Level	_	_	_	100	μW

<sup>&</sup>lt;sup>1</sup> Frequency deviation–refer to center frequency.

#### **DC Electrical Characteristics**

Table 12. DC Electrical Characteristics 1,2

Symbol	Parameter	Conditions	Minimum	Typical	Maximum	Units
		$V_{DD} = V_{DDOUTx} = V_{DD1\_8} = 1.8V$ ; OUT1 = 12MHz, OUT3 = 26MHz, OUT2 off, no load.	_	2.0	_	mA
1	Operation Supply Current	$V_{DD} = V_{DDOUTx} = V_{DD1\_8} = 1.8V$ ; OUT1 = 12MHz, OUT3 = 26MHz, OUT2 off, with load.	_	3.5	_	mA
I <sub>DD</sub>	Operation Supply Current	$V_{DD} = V_{DDOUTx} = V_{DD1\_8} = 1.8V$ ; OUT1 = 26MHz, OUT3 = 26MHz, OUT2 = 32kHz, no load.	_	1.8	_	mA
		$V_{DD} = V_{DDOUTx} = V_{DD1\_8} = 1.8V$ ; OUT1 = 26MHz, OUT3 = 26MHz, OUT2 = 32kHz, with load.	_	3.8	_	mA
I <sub>DDPD</sub>	Power Down Current	PD asserted with V <sub>DD1</sub> <sub>_8</sub> and V <sub>DDOUTx</sub> on, I <sup>2</sup> C programming, 32kHz running.	_	390	_	μA
I <sub>DDSUSPEND</sub>	Power Suspend Current	$V_{\rm DDOUT2}$ off and only $V_{\rm DDOUT1}$ and $V_{\rm DD1\_8}$ on, I <sup>2</sup> C programming, 32kHz running.	_	1.6	2.0	μA

<sup>&</sup>lt;sup>1</sup> Single CMOS driver active.

<sup>&</sup>lt;sup>2</sup> OUT1–3 current measured with 0.5 inches transmission line and no load.



## **Electrical Characteristics-Input Parameters**

Supply Voltage  $V_{DD1~8}$  = 1.8V ±5%,  $V_{DDOUTx}$  = 1.8V ±5%,  $T_A$  = -40°C to +85°C.

Table 13. Electrical Characteristics-Input Parameters <sup>1</sup>

Symbol	Parameter	Conditions	Minimum	Typical	Maximum	Units
I <sub>IL</sub>	Input Leakage Low Current for OE1	V <sub>IN</sub> = GND at OE1 pin.	150	_	5	μA
I <sub>IH</sub>	Input Leakage High Current for OE1	V <sub>IN</sub> = 1.89V.	_	_	20	μΑ
I_OE1	Input Leakage Current	V <sub>IN</sub> = 1.89V at OE1 pin.	_	_	120	μΑ

<sup>&</sup>lt;sup>1</sup> Guaranteed by design and characterization; test in production.

#### DC Electrical Characteristics for 1.8V LVCMOS

 $V_{DD}$  = 1.8V ±5%,  $V_{DDOUTx}$  = 1.8V ±5%,  $T_A$  = -40°C to 85°C.

Table 14. DC Electrical Characteristics - 1.8V LVCMOS

Symbol	Parameter	Conditions	Minimum	Typical	Maximum	Units
V <sub>OH</sub>	Output High Voltage	I <sub>OH</sub> = -8mA.	0.7 × V <sub>DDOUTx</sub>	_	$V_{DDOUTx}$	V
V <sub>OL</sub>	Output Low Voltage	I <sub>OL</sub> = 8mA.	_	_	0.25 × V <sub>DDOUTx</sub>	V
I <sub>OZDD</sub>	Output Leakage Current	Tri-state outputs, V <sub>DDOUTx</sub> = 1.89V.	_	_	3	μA
V <sub>IH</sub>	Input High Voltage	Single-ended inputs – OE, SDA, SCL.	0.65 × V <sub>DDOUTx</sub>	_	$V_{DDOUT}x + 0.3$	V
V <sub>IL</sub>	Input Low Voltage	Single-ended inputs – OE, SDA, SCL.	GND - 0.3	_	0.35 × V <sub>DDOUTx</sub>	V

#### **AC Electrical Characteristics**

#### Table 15. AC Timing Electrical Characteristics - 32.768kHz

 $V_{DD1~8}$  = 1.8V ±5%,  $V_{DDOUTx}$  = 1.8V ±5%,  $T_A$  = -40°C to +85°C; spread spectrum = off.

Symbol	Parameter	Conditions	Minimum	Typical	Maximum	Units
f <sub>OUT</sub>	Initial Frequency	Single-ended clock output limit (LVCMOS).		32.768		kHz
f <sub>OUT_tor</sub> <sup>1</sup>	Frequency Tolerance	At 25°C.	-20		20	ppm
t1	Output Duty Cycle	Measured at 50%.	45		55	%

<sup>&</sup>lt;sup>1</sup> This measurement uses a 3-day average.



#### Table 16. AC Timing Electrical Characteristics - 1.8V

 $V_{DD1~8}$  = 1.8V ±5%,  $V_{DDOUTx}$  = 1.8V ±5%,  $T_A$  = -40°C to +85°C; spread spectrum = off.

Symbol	Parameter	Conditions	Minimum	Typical	Maximum	Units
f <sub>OUT</sub>	Output Frequency	Single-ended clock output limit (LVCMOS).	1	_	125	MHz
t1	Output Duty Cycle	LVCMOS clock < 120MHz.	45	_	55	%
t2	Rise/Fall Time	Single-ended LVCMOS output clock rise and fall time, 20% to 80% of $V_{\rm DDOUT}$ 1.8V.	_	1.0	1.5	ns
		Cycle-to-cycle jitter (peak-to-peak), multiple output frequencies switching, differential outputs (1.8V nominal output voltage).  OUT1 = 25MHz.  OUT2 = 100MHz.  OUT3 = 125MHz.	_	50	200	ps
t3	Clock Jitter	Cycle-to-cycle jitter (peak-to-peak), multiple output frequencies switching, differential outputs (1.8V nominal output voltage).  OUT1 = 24MHz.  OUT2 = 32.768kHz.  OUT3 = 26MHz.	_	50	200	ps
		Cycle-to-cycle jitter (peak-to-peak), multiple output frequencies switching, differential outputs (1.8V nominal output voltage).  OUT1 = 32.768kHz.  OUT2 = 26MHz.  OUT3 = 26MHz.	_	50	200	ps
t5 <sup>2</sup>	Lock Time	PLL lock time from power-up.	_		20	ms
t6	Lock Time	32.768kHz clock low-power, power-up time.	_	10	100	ms
t6 <sup>3</sup>	Lock Time	PLL lock time from shutdown mode.	_	0.1	2	ms

<sup>&</sup>lt;sup>1</sup> Practical lower frequency is determined by loop filter settings.

 $<sup>^2</sup>$  Includes loading the configuration bits from OTP to PLL registers. It does not include OTP programming/write time.

<sup>&</sup>lt;sup>3</sup> Actual PLL lock time depends on the loop configuration.



Table 17. AC Timing Electrical Characteristics, 1.2V / 1.8V

 $V_{DD1\ 8} = 1.8V \pm 5\%$ ,  $V_{DDOUT1} = 1.2V \pm 5\%$ ,  $V_{DDOUT2} = 1.8V \pm 5\%$ ,  $V_{A} = -40^{\circ}$ C to +85°C; spread spectrum = off.

Symbol	Parameter	Conditions	Minimum	Typical	Maximum	Units
f <sub>OUT</sub>	Output Frequency	Single-ended clock output limit (LVCMOS).	1	_	125	MHz
t1	Output Duty Cycle	LVCMOS clock < 120MHz.	45	_	55	%
t2	Rise/Fall Time	OUT2/OUT3 LVCMOS output clock rise and fall time, 20% to 80% of $V_{DDOUT2}$ = 1.8V.	_	1.0	1.5	ns
(2	Nise/i all Time	OUT1 LVCMOS output clock rise and fall time, 20% to 80% of V <sub>DDOUT1</sub> = 1.2V.	_	1.5	2.5	ns
	Cycle-to-cycle jitter (peak-to-peak), multiple output frequencies switching, differential outputs (1.8V nominal output voltage; 1.2V on V <sub>DDOUT1</sub> ).  OUT1 = 25MHz.  OUT2 = 100MHz.  OUT3 = 125MHz.	_	100	350	ps	
15	t3 Clock Jitter	Cycle-to-cycle jitter (peak-to-peak), multiple output frequencies switching, differential outputs (1.8V nominal output voltage; 1.2V on V <sub>DDOUT1</sub> ).  OUT1 = 32.768kHz.  OUT2 = 26MHz.  OUT3 = 26MHz.	_	50	100	ps
t5 <sup>2</sup>	Lock Time	PLL lock time from power-up.	_		20	ms
t6	Lock Time	32.768kHz clock low-power, power-up time.	_	10	100	ms
t6 <sup>3</sup>	Lock Time	PLL lock time from shutdown mode.	_	0.1	2	ms

<sup>&</sup>lt;sup>1</sup> Practical lower frequency is determined by loop filter settings.

# I<sup>2</sup>C Bus DC Characteristics

Table 18. I<sup>2</sup>C Bus DC Characteristics

Symbol	Parameter	Conditions	Minimum	Typical	Maximum	Units
V <sub>IH</sub>	Input High Level	_	0.7 × V <sub>DD1_8</sub>	_	_	V
V <sub>IL</sub>	Input Low Level	_	_	_	0.3 × V <sub>DD1_8</sub>	V
V <sub>HYS</sub>	Hysteresis of Inputs	_	0.05 × V <sub>DD1_8</sub>	_	_	V
I <sub>IN</sub>	Input Leakage Current	_	_	_	±1	μΑ
V <sub>OL</sub>	Output Low Voltage	I <sub>OL</sub> = 3 mA.	_	_	0.4	V

<sup>&</sup>lt;sup>2</sup> Includes loading the configuration bits from OTP to PLL registers. It does not include OTP programming/write time.

<sup>&</sup>lt;sup>3</sup> Actual PLL lock time depends on the loop configuration.



Table 19. I<sup>2</sup>C Bus AC Characteristics

Symbol	Parameter	Minimum	Typical	Maximum	Units
F <sub>SCLK</sub>	Serial Clock Frequency (SCL)	_	100	400	kHz
t <sub>BUF</sub>	Bus Free Time between STOP and START	1.3	_	_	μs
t <sub>SU:START</sub>	Setup Time, START	0.6	_	_	μs
t <sub>HD:START</sub>	Hold Time, START	0.6	_	_	μs
t <sub>SU:DATA</sub>	Setup Time, data input (SDA)	100	_	_	ns
t <sub>HD:DATA</sub>	Hold Time, data input (SDA) <sup>1</sup>	0	_	_	μs
t <sub>OVD</sub>	Output Data Valid from Clock	_	_	0.9	μs
C <sub>B</sub>	Capacitive Load for Each Bus Line	_	_	400	pF
t <sub>R</sub>	Rise Time, data and clock (SDA, SCL)	20 + 0.1 × C <sub>B</sub>	_	300	ns
t <sub>F</sub>	Fall Time, data and clock (SDA, SCL)	20 + 0.1 × C <sub>B</sub>	_	300	ns
t <sub>HIGH</sub>	High Time, clock (SCL)	0.6	_	_	μs
t <sub>LOW</sub>	Low Time, clock (SCL)	1.3	_	_	μs
t <sub>SU:STOP</sub>	Setup Time, STOP	0.6	_	_	μs

<sup>&</sup>lt;sup>1</sup> A device must internally provide a hold time of at least 300ns for the SDA signal (referred to the V<sub>IH(MIN)</sub> of the SCL signal) to bridge the undefined region of the falling edge of SCL.

# **Spread Spectrum Generation Specifications**

**Table 20. Spread Spectrum Generation Specifications** 

Symbol	Parameter	Description	Minimum	Typical	Maximum	Units
f <sub>OUT</sub>	Output Frequency	Output frequency range.	1	_	125	MHz
f <sub>MOD</sub>	Mod Frequency	Modulation frequency.	3	30 to 63		
f <sub>SPREAD</sub>	Spread Value	Amount of spread value (programmable)–down spread.	-0.5% to -2%		% f <sub>OUT</sub>	
%tolerance	Spread% Value	Variation of spread range.	_	15	_	%



#### **General SMBus Serial Interface Information**

#### **How to Write**

- Controller (host) sends a start bit
- Controller (host) sends the write address
- IDT clock will acknowledge
- Controller (host) sends the beginning byte location = N
- IDT clock will acknowledge
- Controller (host) sends the byte count = X
- IDT clock will acknowledge
- Controller (host) starts sending Byte N through Byte N+X-1
- IDT clock will acknowledge each byte one at a time
- Controller (host) sends a stop bit

	Index Bloc	k W	rite Operation
Contro	ller (Host)		IDT (Slave/Receiver)
T	starT bit		
Slave	Address		
WR	WRite		
			ACK
Beginnir	ng Byte = N		
			ACK
Data Byt	e Count = X		
			ACK
Beginn	ing Byte N		
			ACK
0		1 ↓	
0		X Byte	0
0		e e	0
		1	0
Byte I	N + X - 1		
			ACK
Р	stoP bit	1	

#### **How to Read**

- Controller (host) will send a start bit
- Controller (host) sends the write address
- IDT clock will acknowledge
- Controller (host) sends the beginning byte location = N
- IDT clock will acknowledge
- Controller (host) will send a separate start bit
- Controller (host) sends the read address
- IDT clock will acknowledge
- IDT clock will send the data byte count = X
- IDT clock sends Byte N+X-1
- IDT clock sends Byte 0 through Byte X (if X<sub>(H)</sub> was written to Byte 8)
- Controller (host) will need to acknowledge each byte
- Controller (host) will send a not acknowledge bit
- Controller (host) will send a stop bit

	Index Block F	Read Op	peration
Co	ontroller (Host)		IDT (Slave/Receiver)
Т	starT bit		
	Slave Address		
WR	WRite		
			ACK
Be	ginning Byte = N		
			ACK
RT	Repeat starT		
(	Slave Address		
RD	ReaD		
			ACK
			Data Byte Count=X
	ACK		
			Beginning Byte N
	ACK		
		υ	0
	0	X Byte	0
	0	×	0
	0		
			Byte N + X - 1
N	Not acknowledge		
Р	stoP bit		



#### **SMBus Table Byte 0: General Control**

Byte 00h	Name	Control Function	Туре	0	1	PWD
Bit 7	OTP_Burned	OTP memory programming indication	R/W	OTP memory non-programmed	OTP memory programmed	0
Bit 6	I2C_addr[1]	I <sup>2</sup> C address select bit 1	R/W	00: D0 / 10: D4 /	/ 01: D2 / 11: D6	0
Bit 5	I2C_addr[0]	I <sup>2</sup> C address select bit 0	R/W	_	_	0
Bit 4	PLL1_SSEN	PLL1 Spread Spectrum enable	R/W	disable	enable	0
Bit 3	Reserved	Reserved	R/W	_	_	0
Bit 2	PLL3_refin_sel	PLL3 source selection	R/W	Xtal	Seed (DIV2)	0
Bit 1	Reserved	Reserved	R/W	_	_	0
Bit 0	OTP_protect	OTP memory protection	R/W	read/write	write locked	0

#### SMBus Table Byte 1: Dash Code (optional)

Byte 01h	Name	Control Function	Туре	0	1	PWD
Bit 7	DashCode ID[7]	Dash code ID	R/W	_	_	0
Bit 6	DashCode ID[6]	Dash code ID	R/W	_	_	0
Bit 5	DashCode ID[5]	Dash code ID	R/W	_	_	0
Bit 4	DashCode ID[4]	Dash code ID	R/W	_	_	0
Bit 3	DashCode ID[3]	Dash code ID	R/W	_	_	0
Bit 2	DashCode ID[2]	Dash code ID	R/W	_	_	0
Bit 1	DashCode ID[1]	Dash code ID	R/W	_	_	0
Bit 0	DashCode ID[0]	Dash code ID	R/W	_	_	0

#### **SMBus Table Byte 2: Crystal Cap Setting**

Byte 02h	Name	Control Function	Туре	0	1	PWD
Bit 7		Reserved	R/W	_	_	0
Bit 6		Reserved	R/W	_	_	0
Bit 5		Reserved	R/W	_	_	0
Bit 4		Reserved	R/W	_	_	1
Bit 3		Reserved	R/W	_	_	0
Bit 2		Reserved	R/W	_	_	0
Bit 1		Reserved	R/W	_	_	0
Bit 0		Reserved	R/W	_	_	1

15



#### SMBus Table Byte 3: PLL3 M Divider

Byte 03h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL3_MDIV1	PLL3 source clock divider	R/W	disable M DIV1	bypadd divider (/1)	0
Bit 6	PLL3_MDIV2	PLL3 source clock divider	R/W	disable M DIV2	bypadd divider (/2)	0
Bit 5	PLL3 M_DIV[5]	PLL3 reference integer divider	R/W			0
Bit 4	PLL3 M_DIV[4]	PLL3 reference integer divider	R/W			1
Bit 3	PLL3 M_DIV[3]	PLL3 reference integer divider	R/W	3 64 4	ofoult is 26	1
Bit 2	PLL3 M_DIV[2]	PLL3 reference integer divider	R/W	-		0
Bit 1	PLL3 M_DIV[1]	PLL3 reference integer divider	R/W			1
Bit 0	PLL3 M_DIV[0]	PLL3 reference integer divider	R/W			0

#### SMBus Table Byte 4: PLL3 N Divider

Byte 04h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL3 N_DIV[7]	PLL3 VCO feedback integer divider bit7	R/W	12–2048, default VCO setting is		1
Bit 6	PLL3 N_DIV[6]	PLL3 VCO feedback integer divider bit6	R/W			1
Bit 5	PLL3 N_DIV[5]	PLL3 VCO feedback integer divider bit5	R/W			1
Bit 4	PLL3 N_DIV[4]	PLL3 VCO feedback integer divider bit4	R/W			0
Bit 3	PLL3 N_DIV[3]	PLL3 VCO feedback integer divider bit3	R/W	480	MHz	0
Bit 2	PLL3 N_DIV[2]	PLL3 VCO feedback integer divider bit2	R/W			0
Bit 1	PLL3 N_DIV[1]	PLL3 VCO feedback integer divider bit1	R/W			0
Bit 0	PLL3 N_DIV[0]	PLL3 VCO feedback integer divider bit0	R/W			0

#### SMBus Table Byte 5: PLL3 Loop Filter Setting and N Divider 10:8

Byte 05h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL3_R100K	PLL3 Loop filter resister 100kΩ	R/W	bypass	plus 100kΩ	0
Bit 6	PLL3_R50K	PLL3 Loop filter resister 50kΩ	R/W	bypass	plus 50kΩ	0
Bit 5	PLL3_R25K	PLL3 Loop filter resister 25kΩ	R/W	bypass	plus 25kΩ	0
Bit 4	PLL3_R12.5K	PLL3 Loop filter resister 12.5kΩ	R/W	bypass	plus 12.5kΩ	1
Bit 3	PLL3_R6K	PLL3 Loop filter resister 6kΩ	R/W	bypass	only 6kΩ applied	0
Bit 2	PLL3 N_DIV[10]	PLL3 VCO feedback integer divider bit10	R/W			0
Bit 1	PLL3 N_DIV[9]	PLL3 VCO feedback integer divider bit9	R/W	12–2048, default VCO setting is 480MHz		0
Bit 0	PLL3 N_DIV[8]	PLL3 VCO feedback integer divider bit8	R/W	100	···· <u>-</u>	1



#### **SMBus Table Byte 6: PLL3 Charge Pump Control**

Byte 06h	Name	Control Function	Туре	0	1	PWD
Bit 7	OUTDIV 3 Source	Output divider 3 source clock selection	R/W	PLL2	DIV4seed	0
Bit 6	PLL3_CP_8X	PLL3 charge pump control	R/W	_	x8	1
Bit 5	PLL3_CP_4X	PLL3 charge pump control	R/W	_	x4	1
Bit 4	PLL3_CP_2X	PLL3 charge pump control	R/W	_	x2	0
Bit 3	PLL3_CP_1X	PLL3 charge pump control	R/W	_	x1	1
Bit 2	PLL3_CP_/24	PLL3 charge pump control	R/W	_	/24	1
Bit 1	PLL3_CP_/3	PLL3 charge pump control	R/W	_	/3	0
Bit 0	PLL3_SIREF	PLL3 SiRef current selection	R/W	10μΑ	20μΑ	0

Note: Formula: (iRef (10 $\mu$ A) × (1+SiRef) × (1 × 1X + 2 × 2X + 4 × 4X + 8 × 8X + 16 × 16X)) / ((24 × /24) + (3 × /3))

#### **SMBus Table Byte 7: PLL1 Control and OUTDIV5 Divider**

Byte 07h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL1_MDIV_Doubler	PLL1 reference clock doubler	R/W	disable	enable	0
Bit 6	PLL1_SIREF	PLL1 SiRef current selection	R/W	10.8μΑ	21.6µA	0
Bit 5	PLL1_EN_CH2	PLL1 output Channel 2 control	R/W	disable	enable	1
Bit 4	PLL1_EN_3rdpole	PLL1 3rd pole control	R/W	disable	enable	0
Bit 3	OUTDIV5[3]	Output divider5 control bit 3	R/W			0
Bit 2	OUTDIV5[2]	Output divider5 control bit 2	R/W	DIV5[3:2] = 1,2,4,5; DIV5[1:0] = 1,3,5,10; Default Divider = 1 × 10 = 10		0
Bit 1	OUTDIV5[1]	Output divider5 control bit 1	R/W			1
Bit 0	OUTDIV5[0]	Output divider5 control bit 0	R/W			1

#### **SMBus Table Byte 8: PLL1 M Divider**

Byte 08h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL1_MDIV1	PLL3 VCO reference clock divider 1	R/W	disable M DIV1	bypass divider (/1)	0
Bit 6	PLL1_MDIV2	PLL3 VCO reference clock divider 2	R/W	disable M DIV2	bypass divider (/2)	0
Bit 5	PLL1 M_DIV[5]	PLL1 reference clock divider control bit 5	R/W			0
Bit 4	PLL1 M_DIV[4]	PLL1 reference clock divider control bit 4	R/W			1
Bit 3	PLL1 M_DIV[3]	PLL1 reference clock divider control bit 3	R/W	3 64 da	fault is 26	1
Bit 2	PLL1 M_DIV[2]	PLL1 reference clock divider control bit 2	R/W	3-04, de	iduit is 20	0
Bit 1	PLL1 M_DIV[1]	PLL1 reference clock divider control bit 1	R/W			1
Bit 0	PLL1 M_DIV[0]	PLL1 reference clock divider control bit 0	R/W			0



#### SMBus Table Byte 9: PLL1 VCO N Divider

Byte 09h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL1 N_DIV[7]	PLL1 VCO feedback divider control bit 7	R/W	12–2048, default is 600		0
Bit 6	PLL1 N_DIV[6]	PLL1 VCO feedback divider control bit 6	R/W			1
Bit 5	PLL1 N_DIV[5]	PLL1 VCO feedback divider control bit 5	R/W			0
Bit 4	PLL1 N_DIV[4]	PLL1 VCO feedback divider control bit 4	R/W			1
Bit 3	PLL1 N_DIV[3]	PLL1 VCO feedback divider control bit 3	R/W	12–2040, ui	elault is 000	1
Bit 2	PLL1 N_DIV[2]	PLL1 VCO feedback divider control bit 2	R/W			0
Bit 1	PLL1 N_DIV[1]	PLL1 VCO feedback divider control bit 1	R/W			0
Bit 0	PLL1 N_DIV[0]	PLL1 VCO feedback divider control bit 0	R/W			0

#### SMBus Table Byte 10: PLL Loop Filter and N Divider

Byte 0Ah	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL1_R100K	PLL1 loop filter resister 100kΩ	R/W	bypass	plus 100kΩ	1
Bit 6	PLL1_R50K	PLL1 loop filter resister 50kΩ	R/W	bypass	plus 50kΩ	0
Bit 5	PLL1_R25K	PLL1 loop filter resister 25kΩ	R/W	bypass	plus 25kΩ	1
Bit 4	PLL1_R12.5K	PLL1 loop filter resister 12.5kΩ	R/W	bypass	plus 12.5kΩ	1
Bit 3	PLL1_R1.0K	PLL1 loop filter resister 1kΩ	R/W	bypass	only 1.0kΩ applied	0
Bit 2	PLL1 N_DIV[10]	PLL1 VCO feedback integer divider bit 10	R/W			0
Bit 1	PLL1 N_DIV[9]	PLL1 VCO feedback integer divider bit 9	R/W	12–2048, default is 600		1
Bit 0	PLL1 N_DIV[8]	PLL1 VCO feedback integer divider bit 8	R/W			0

#### SMBus Table Byte 11: PLL1 Charge Pump

Byte 0Bh	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL1_CP_32X	PLL1 charge pump control	R/W	_	x32	0
Bit 6	PLL1_CP_16X	PLL1 charge pump control	R/W	_	x16	0
Bit 5	PLL1_CP_8X	PLL1 charge pump control	R/W	_	x8	0
Bit 4	PLL1_CP_4X	PLL1 charge pump control	R/W	_	x4	0
Bit 3	PLL1_CP_2X	PLL1 charge pump control	R/W	_	x2	0
Bit 2	PLL1_CP_1X	PLL1 charge pump control	R/W	_	x1	1
Bit 1	PLL1_CP_/24	PLL1 charge pump control	R/W	_	/24	1
Bit 0	PLL1_CP_/3	PLL1 charge pump control	R/W	_	/3	0



#### **SMBus Table Byte 12: PLL1 Spread Spectrum Control**

Byte 0Ch	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL1_SS_REFDIV23	PLL1 spread spectrum control- Ref divider 23	R/W	_	_	0
Bit 6	PLL1_SS_REFDIV[6]	PLL1 spread spectrum control- Ref divider 6	R/W	_	_	0
Bit 5	PLL1_SS_REFDIV[5]	PLL1 spread spectrum control- Ref divider 5	R/W	_	_	0
Bit 4	PLL1_SS_REFDIV[4]	PLL1 spread spectrum control- Ref divider 4	R/W	_	_	0
Bit 3	PLL1_SS_REFDIV[3]	PLL1 spread spectrum control- Ref divider 3	R/W	_	_	0
Bit 2	PLL1_SS_REFDIV[2]	PLL1 spread spectrum control- Ref divider 2	R/W	_	_	0
Bit 1	PLL1_SS_REFDIV[1]	PLL1 spread spectrum control- Ref divider 1	R/W	_	_	0
Bit 0	PLL1_SS_REFDIV[0]	PLL1 spread spectrum control- Ref divider 0	R/W	_	_	0

#### **SMBus Table Byte 13: PLL1 Spread Spectrum Control**

Byte 0Dh	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL1_SS_FBDIV[7]	PLL1 spread spectrum - feedback divider 7	R/W	_	_	0
Bit 6	PLL1_SS_FBDIV[6]	PLL1 spread spectrum - feedback divider 6	R/W	_	_	0
Bit 5	PLL1_SS_FBDIV[5]	PLL1 spread spectrum - feedback divider 5	R/W	_	_	0
Bit 4	PLL1_SS_FBDIV[4]	PLL1 spread spectrum - feedback divider 4	R/W	_	_	0
Bit 3	PLL1_SS_FBDIV[3]	PLL1 spread spectrum - feedback divider 3	R/W	_	_	0
Bit 2	PLL1_SS_FBDIV[2]	PLL1 spread spectrum - feedback divider 2	R/W	_	_	0
Bit 1	PLL1_SS_FBDIV[1]	PLL1 spread spectrum - feedback divider 1	R/W	_	_	0
Bit 0	PLL1_SS_FBDIV[0]	PLL1 spread spectrum - feedback divider 0	R/W	_	_	0

#### **SMBus Table Byte 14: PLL1 Spread Spectrum Control**

Byte 0Eh	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL1_SS_FBDIV[15]	PLL1 spread spectrum - feedback divider 15	R/W	_	_	0
Bit 6	PLL1_SS_FBDIV[14]	PLL1 spread spectrum - feedback divider 14	R/W	_	_	0
Bit 5	PLL1_SS_FBDIV[13]	PLL1 spread spectrum - feedback divider 13	R/W	_	_	0
Bit 4	PLL1_SS_FBDIV[12]	PLL1 spread spectrum - feedback divider 12	R/W	_	_	0
Bit 3	PLL1_SS_FBDIV[11]	PLL1 spread spectrum - feedback divider 11	R/W	_	_	0
Bit 2	PLL1_SS_FBDIV[10]	PLL1 spread spectrum - feedback divider 10	R/W	_	_	0
Bit 1	PLL1_SS_FBDIV[09]	PLL1 spread spectrum - feedback divider 9	R/W	_	_	0
Bit 0	PLL1_SS_FBDIV[08]	PLL1 spread spectrum - feedback divider 8	R/W	_	_	0



#### **SMBus Table Byte 15: Output Divider 1 Control**

Byte 0Fh	Name	Control Function	Туре	0	1	PWD
Bit 7	OUTDIV1[3]	Output divider1 control bit 3	R/W	DIV1[3:2]=1,2,4,8; DIV1[1:0]=1,4,5,6; Default divider = 1x1=1		0
Bit 6	OUTDIV1[2]	Output divider1 control bit 2	R/W			0
Bit 5	OUTDIV1[1]	Output divider1 control bit 1	R/W			0
Bit 4	OUTDIV1[0]	Output divider1 control bit 0	R/W			0
Bit 3	OUTDIV2[3]	Output divider2 control bit 3	R/W			0
Bit 2	OUTDIV2[2]	Output divider2 control bit 2	R/W		DIV2[1:0]=1,3,5,10;	0
Bit 1	OUTDIV2[1]	Output divider2 control bit 1	R/W	Default divider = 1x10=10	1	
Bit 0	OUTDIV2[0]	Output divider2 control bit 0	R/W			1

#### SMBus Table Byte 16: PLL2 Integer Feedback Divider

Byte 10h	Name	Control Function	Туре	0	1	PWD
Bit 7		Reserved	R/W	_	_	0
Bit 6		Reserved	R/W	_	_	0
Bit 5		Reserved		_	_	0
Bit 4	Reserved		R/W	_	_	0
Bit 3		Reserved	R/W	_	_	0
Bit 2	PLL2_FB_INT[10]	PLL2 feedback integer divider 10	R/W	_	_	0
Bit 1	PLL2_FB_INT[9]	PLL2 feedback integer divider 9	R/W	_	_	0
Bit 0	PLL2_FB_INT[8]	PLL2 feedback integer divider 8	R/W	_	_	0

#### SMBus Table Byte 17: PLL2 Integer Feedback Divider

Byte 11h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL2_FB_INT_DIV[7]	PLL2 feedback integer divider 7	R/W	_	_	0
Bit 6	PLL2_FB_INT_DIV[6]	PLL2 feedback integer divider 6	R/W	_	_	0
Bit 5	PLL2_FB_INT_DIV[5]	PLL2 feedback integer divider 5	R/W	_	_	1
Bit 4	PLL2_FB_INT_DIV[4]	PLL2 feedback integer divider 4	R/W	_	_	1
Bit 3	PLL2_FB_INT_DIV[3]	PLL2 feedback integer divider 3	R/W	_	_	1
Bit 2	PLL2_FB_INT_DIV[2]	PLL2 feedback integer divider 2	R/W	_	_	1
Bit 1	PLL2_FB_INT_DIV[1]	PLL2 feedback integer divider 1	R/W	_	_	0
Bit 0	PLL2_FB_INT_DIV[0]	PLL2 feedback integer divider 0	R/W		_	0



#### SMBus Table Byte 18: PLL2 Fractional Feedback Divider

Byte 12h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL2_FB_FRC_DIV[7]	PLL2 feedback fractional divider 7	R/W	_	_	0
Bit 6	PLL2_FB_FRC_DIV[6]	PLL2 feedback fractional divider 6	R/W	_	_	0
Bit 5	PLL2_FB_FRC_DIV[5]	PLL2 feedback fractional divider 5	R/W	_	_	0
Bit 4	PLL2_FB_FRC_DIV[4]	PLL2 feedback fractional divider 4	R/W	_	_	0
Bit 3	PLL2_FB_FRC_DIV[3]	PLL2 feedback fractional divider 3	R/W	_	_	0
Bit 2	PLL2_FB_FRC_DIV[2]	PLL2 feedback fractional divider 2	R/W	_	_	0
Bit 1	PLL2_FB_FRC_DIV[1]	PLL2 feedback fractional divider 1	R/W	_	_	0
Bit 0	PLL2_FB_FRC_DIV[0]	PLL2 feedback fractional divider 0	R/W	_	_	0

#### SMBus Table Byte 19: PLL2 Fractional Feedback Divider

Byte 13h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL2_FB_FRC_DIV[15]	PLL2 feedback fractional divider 15	R/W	_	_	0
Bit 6	PLL2_FB_FRC_DIV[14]	PLL2 feedback fractional divider 14	R/W	_	_	0
Bit 5	PLL2_FB_FRC_DIV[13]	PLL2 feedback fractional divider 13	R/W	_	_	0
Bit 4	PLL2_FB_FRC_DIV[12]	PLL2 feedback fractional divider 12	R/W	_	_	0
Bit 3	PLL2_FB_FRC_DIV[11]	PLL2 feedback fractional divider 11	R/W	_	_	0
Bit 2	PLL2_FB_FRC_DIV[10]	PLL2 feedback fractional divider 10	R/W	_	_	0
Bit 1	PLL2_FB_FRC_DIV[9]	PLL2 feedback fractional divider 9	R/W	_	_	0
Bit 0	PLL2_FB_FRC_DIV[8]	PLL2 feedback fractional divider 8	R/W	_	_	0

#### **SMBus Table Byte 20: PLL2 Spread Spectrum Control**

Byte 14h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL2_STEP[7]	PLL2 spread step size control bit 7	R/W	_	_	0
Bit 6	PLL2_STEP[6]	PLL2 spread step size control bit 6	R/W	_	_	0
Bit 5	PLL2_STEP[5]	PLL2 spread step size control bit 5	R/W	_	_	0
Bit 4	PLL2_STEP[4]	PLL2 spread step size control bit 4	R/W	_	_	0
Bit 3	PLL2_STEP[3]	PLL2 spread step size control bit 3	R/W	_	_	0
Bit 2	PLL2_STEP[2]	PLL2 spread step size control bit 2	R/W	_	_	0
Bit 1	PLL2_STEP[1]	PLL2 spread step size control bit 1	R/W	_	_	0
Bit 0	PLL2_STEP[0]	PLL2 spread step size control bit 0	R/W		_	0



#### **SMBus Table Byte 21: PLL2 Spread Spectrum Control**

Byte 15h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL2_STEP[15]	PLL2 spread step size control bit 15	R/W	_	_	0
Bit 6	PLL2_STEP[14]	PLL2 spread step size control bit 14	R/W	_	_	0
Bit 5	PLL2_STEP[13]	PLL2 spread step size control bit 13	R/W	_	_	0
Bit 4	PLL2_STEP[12]	PLL2 spread step size control bit 12	R/W	_	_	0
Bit 3	PLL2_STEP[11]	PLL2 spread step size control bit 11	R/W	_	_	0
Bit 2	PLL2_STEP[10]	PLL2 spread step size control bit 10	R/W	_	_	0
Bit 1	PLL2_STEP[9]	PLL2 spread step size control bit 9	R/W	_	_	0
Bit 0	PLL2_STEP[8]	PLL2 spread step size control bit 8	R/W	_	_	0

#### **SMBus Table Byte 22: PLL2 Spread Spectrum Control**

Byte 16h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL2_STEP_DELTA[7]	PLL2 spread step size control delta bit 7	R/W	_	_	0
Bit 6	PLL2_STEP_DELTA[6]	PLL2 spread step size control delta bit 6	R/W	_	_	0
Bit 5	PLL2_STEP_DELTA[5]	PLL2 spread step size control delta bit 5	R/W	_	_	0
Bit 4	PLL2_STEP_DELTA[4]	PLL2 spread step size control delta bit 4	R/W	_	_	0
Bit 3	PLL2_STEP_DELTA[3]	PLL2 spread step size control delta bit 3	R/W	_	_	0
Bit 2	PLL2_STEP_DELTA[2]	PLL2 spread step size control delta bit 2	R/W	_	_	0
Bit 1	PLL2_STEP_DELTA[1]	PLL2 spread step size control delta bit 1	R/W	_	_	0
Bit 0	PLL2_STEP_DELTA[0]	PLL2 spared step size control delta bit 0	R/W	_	_	0

#### **SMBus Table Byte 23: PLL2 Period Control**

Byte 17h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL2_PERIOD[7]	PLL2 period control bit 7	R/W	_	_	0
Bit 6	PLL2_PERIOD[6]	PLL2 period control bit 6	R/W	_	_	0
Bit 5	PLL2_PERIOD[5]	PLL2 period control bit 5	R/W	_	_	0
Bit 4	PLL2_PERIOD[4]	PLL2 period control bit 4	R/W	_	_	0
Bit 3	PLL2_PERIOD[3]	PLL2 period control bit 3	R/W	_	_	0
Bit 2	PLL2_PERIOD[2]	PLL2 period control bit 2	R/W	_	_	0
Bit 1	PLL2_PERIOD[1]	PLL2 period control bit 1	R/W	_	_	0
Bit 0	PLL2_PERIOD[0]	PLL2 period control bit 0	R/W	_	_	0



#### **SMBus Table Byte 24: PLL2 Control Register**

Byte 18h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL2_PERIOD[9]	PLL2 period control bit 9	R/W	_	_	0
Bit 6	PLL2_PERIOD[8]	PLL2 period control bit 8	R/W	_	_	0
Bit 5	PLL2_SSEN	PLL2 spread spectrum enable	R/W	disable	enable	0
Bit 4	PLL2_R100K	PLL2 Loop filter resister 100kΩ	R/W	bypass	plus 100kΩ	0
Bit 3	PLL2_R50K	PLL2 Loop filter resister 50kΩ	R/W	bypass	plus 50kΩ	1
Bit 2	PLL2_R25K	PLL2 Loop filter resister 25kΩ	R/W	bypass	plus 25kΩ	1
Bit 1	PLL2_R12.5K	PLL2 Loop filter resister 12.5kΩ	R/W	bypass	plus 12.5kΩ	1
Bit 0	PLL2_R6K	PLL2 Loop filter resister 6kΩ	R/W	bypass	only 6kΩ applied	0

#### **SMBus Table Byte 25: PLL2 Charge Pump Control**

Byte 19h	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL2_CP_16X	PLL2 charge pump control	R/W	_	x16	0
Bit 6	PLL2_CP_8X	PLL2 charge pump control	R/W	_	x8	0
Bit 5	PLL2_CP_4X	PLL2 charge pump control	R/W	_	x4	0
Bit 4	PLL2_CP_2X	PLL2 charge pump control	R/W	_	x2	1
Bit 3	PLL2_CP_1X	PLL2 charge pump control	R/W	_	x1	0
Bit 2	PLL2_CP_/24	PLL2 charge pump control	R/W	_	/24	1
Bit 1	PLL2_CP_/3	PLL2 charge pump control	R/W	_	/3	0
Bit 0	PLL2_SIREF	PLL2 SiRef current selection	R/W	10μΑ	20μΑ	0

#### SMBus Table Byte 26: PLL2 M Divider Setting

Byte 1Ah	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL2_MDIV_Doubler	PLL2 reference divider - doubler	R/W	disable	enable	0
Bit 6	PLL2_MDIV1	PLL2 reference divider 1	R/W	disable M DIV1	bypadd divider (/1)	0
Bit 5	PLL2_MDIV2	PLL2 reference divider 2	R/W	disable M DIV2	bypadd divider (/2)	0
Bit 4	PLL2_MDIV[4]	PLL2 reference divider control bit 4	R/W			1
Bit 3	PLL2_MDIV[3]	PLL2 reference divider control bit 3	R/W			1
Bit 2	PLL2_MDIV[2]	PLL2 reference divider control bit 2	R/W	3-64, de	fault is 26	0
Bit 1	PLL2_MDIV[1]	PLL2 reference divider control bit 1	R/W			1
Bit 0	PLL2_MDIV[0]	PLL2 reference divider control bit 0	R/W			0



#### SMBus Table Byte 27: Output Divider 4

Byte 1Bh	Name	Control Function	Туре	0	1	PWD
Bit 7	OUTDIV3[3]	Out divider 4 control bit 7	R/W	DIV3[3:2]=1,2,4,5; DIV3[1:0]=1,3,5,10; Default divider = 1x5=5		0
Bit 6	OUTDIV3[2]	Out divider 4 control bit 6	R/W			0
Bit 5	OUTDIV3[1]	Out divider 4 control bit 5	R/W			1
Bit 4	OUTDIV3[0]	Out divider 4 control bit 4	R/W			0
Bit 3	OUTDIV4[3]	Out divider 4 control bit 3	R/W			0
Bit 2	OUTDIV4[2]	Out divider 4 control bit 2	R/W	DIV4[3:2]=1,2,4,8;	DIV4[1:0]=1,3,5,10;	0
Bit 1	OUTDIV4[1]	Out divider 4 control bit 1	R/W	Default divider = 1x10=10	1	
Bit 0	OUTDIV4[0]	Out divider 4 control bit 0	R/W			1

#### **SMBus Table Byte 28: PLL Operation Control Register**

Byte 1Ch	Name	Control Function	Туре	0	1	PWD
Bit 7	PLL2_HRS_EN	PLL2 spread high resolution selection enable	R/W	normal	enable (shift 4 bits)	0
Bit 6	PLL2_refin_sel	PLL2 reference clock source select	R/W	Xtal	DIV2	0
Bit 5	PLL3_PDB	PLL3 power down	R/W	power down	running	0
Bit 4	PLL3_LCKBYPSSB	PLL3 lock bypass	R/W	bypass lock	lock	0
Bit 3	PLL2_PDB	PLL2 power down	R/W	power down	running	1
Bit 2	PLL2_LCKBYPSSB	PLL2 lock bypass	R/W	bypass lock	lock	1
Bit 1	PLL1_PDB	PLL1 power down	R/W	power down	running	0
Bit 0	PLL1_LCKBYPSSB	PLL1 lock bypass	R/W	bypass lock	lock	0

#### **SMBus Table Byte 29: Output Control**

Byte 1Dh	Name	Control Function	Туре	0	1	PWD
Bit 7		Reserved	R/W	_	_	0
Bit 6		Reserved		_	_	0
Bit 5		Reserved		_	_	1
Bit 4		Reserved		_	_	1
Bit 3		Reserved	R/W	_	_	0
Bit 2		Reserved	R/W	_	_	0
Bit 1	Reserved		R/W	_	_	0
Bit 0		Reserved		_	_	0



#### **SMBus Table Byte 30: OE and DFC Control**

Byte 1Eh	Name	Control Function	Туре	0	1	PWD
Bit 7	OUT1_EN	OUT1 output enable control	R/W	disable	enable	1
Bit 6	OE1_fun_sel[1]	OE1 pin function selection bit 1	R/W	11:DFC0 10: OUT1_PPS 01: PD# 00: OUT1 OE		0
Bit 5	OE1_fun_sel[0]	OE1 pin function selection bit 0	R/W			0
Bit 4	OUT3_EN	OUT3 output enable control	R/W	disable	enable	1
Bit 3		Reserved	R/W	_	_	0
Bit 2		Reserved	R/W	_	_	0
Bit 1	DFC_SW_Sel[1]	DFC frequency select bit 1	R/W	00: N0 01: N1 10:N2 11:N3		0
Bit 0	DFC_SW_Sel[0]	DFC frequency select bit 0	R/W			0

#### **SMBus Table Byte 31: Control Register**

Byte 1Fh	Name	Control Function	Туре	0	1	PWD
Bit 7	OUT2 free run_b	OUT2 free run_b	R/W	freerun	stoppable	1
Bit 6	Reserved		R/W	_	_	0
Bit 5	Reserved		R/W	_	_	0
Bit 4	Reserved		R/W	_	_	0
Bit 3		Reserved	R/W	_	_	0
Bit 2	PLL2_3rd_EN_CFG	PLL2 3rd order control	R/W	1st order	3rd order	1
Bit 1	OUTDIV5 source	OUTDIV5 source	R/W	PLL3	DIV4seed	0
Bit 0	PLL2_EN_3rdpole	PLL2 3rd Pole control	R/W	disable	enable	0

#### **SMBus Table Byte 32: Control Register**

Byte 20h	Name Control Function		Туре	0	1	PWD
Bit 7	OUT2_EN OUT2 output enable control			disable	enable	1
Bit 6	Reserved		R/W	_	_	0
Bit 5	Reserved		R/W	_	_	0
Bit 4	DFC_EN DFC function control		R/W	disable	enable	0
Bit 3	Reserved		R/W	_	_	0
Bit 2	Reserved		R/W	_	_	0
Bit 1	Reserved			_	_	0
Bit 0	Reserved		R/W	_	_	0



#### **SMBus Table Byte 33: OUT3 Control Register**

Byte 21h	Name Control Function		Туре	0	1	PWD
Bit 7	OUT3 free run_b OUT3 free run_b			freerun	stoppable	1
Bit 6	Reserved			_	_	0
Bit 5	Reserved			_	_	0
Bit 4	Reserved			_	_	0
Bit 3	Reserved			_	_	0
Bit 2	Reserved		R/W	_	_	0
Bit 1	Reserved			_	_	0
Bit 0	Reserved		R/W	_	_	0

#### **SMBus Table Byte 34: Control Register**

Byte 22h	Name	Control Function	Туре	0	1	PWD
Bit 7	Reserved		R/W	_	_	1
Bit 6	Reserved		R/W	_	_	1
Bit 5	Reserved		R/W	_	_	1
Bit 4	Reserved		R/W	_	_	1
Bit 3	Reserved		R/W	_	_	0
Bit 2	Reserved		R/W	_	_	1
Bit 1	Reserved		R/W	_	_	0
Bit 0	Reserved		R/W	_	_	0

#### **SMBus Table Byte 35: Control Register**

Byte 23h	Name	Control Function	Туре	0	1	PWD
Bit 7	OUT3 muxsel1	OUT3 muxsel1	R/W	00: DIV3 01: DIV5 10: DIV1 11: CLK_32K		1
Bit 6	OUT3 muxsel0	OUT3 muxsel0	R/W			0
Bit 5	OUT2 muxsel1	OUT2 muxsel1	R/W	00: DIV3 01: DIV5 10: DIV1 11: CLK_32K		0
Bit 4	OUT2 muxsel0	OUT2 muxsel0	R/W			0
Bit 3	OUT1 muxsel1	OUT1 muxsel1	R/W	00: DIV3 01: DIV5 10: DIV1 11: CLK_32K		1
Bit 2	OUT1 muxsel0	OUT1 muxsel0	R/W			1
Bit 1	DIV1 muxsel1	DIV1 muxsel1	R/W	00: PLL1	01: REF	0
Bit 0	DIV1 muxsel0	DIV1 muxsel0	R/W	1x: DIV4outseed		1

26



#### **SMBus Table Byte 36: OUT1 and DIV4 Control**

Byte 24h	Name Control Function		Туре	0	1	PWD
Bit 7	I2C_PDB	Chip power down control bit	R/W	power down	normal	1
Bit 6	Ref_free_run	Reference clock output (OUT2/OUT3)	R/W	stop	freerun	0
Bit 5	free_run_output_config	Clocks free run control	R/W	OUT2 freerun	OUT2/3 freerun	0
Bit 4	Reserved		R/W	_	_	1
Bit 3	OUT1_Freerun_b	OUT1 free run_b	R/W	freerun	stoppable	1
Bit 2	Enable OE2/3	Enable OE2/OE3 function	R/W	Disable	Enable	0
Bit 1	DIV4 muxsel1	DIV4 muxsel1	R/W	00: PLL2_CH2	01: PLL3_CH2	1
Bit 0	DIV4 muxsel0	DIV4 muxsel0	R/W	10: DIV3seed	11: DIV5seed	1

# 5X2503 Datasheet

**Figure** 


NDG12 Package Drawing - page


**Package** 

**Outline** 

Drawings

# RENESAS





RECOMMENDED LAND PATTERN

#### NOTES:

- 1. ALL DIMENSIONS ARE IN mm. ANGLES IN DEGREES.
- 2. TOP DOWN VIEW. AS VIEWED ON PCB.
- 3. COMPONENT OUTLINE SHOWS FOR REFERENCE IN GREEN.
- 4. LAND PATTERN IN BLUE. NSMD PATTERN ASSUMED.
- 5. LAND PATTERN RECOMMENDATION PER IPC-7351B GENERIC REQUIREMENT FOR SURFACE MOUNT DESIGN AND LAND PATTERN.

TOLERANCI UNLESS SE DECIMAL X± .1 XX± .05 XXX± .030	PECIFIED ANGULAR ±1*	WW.	IDT™ w.IDT.com	6024 Silver ( San Jose CA PHONE: (408) FAX: (408) 2	95138 ) 284–8200	•
APPROVAL DRAWN RA CHECKED		TITLE	ND/NDG12 PAC 2.50 x 2.50 m 0.40 mm PITC	nm BODY	NE	
		SIZE	DRAWING No. PSC-	4665		REV 00
		DO NO	OT SCALE DRAWING		SHEET 2	OF 2

REVISIONS

DESCRIPTION

INITIAL RELEASE

REV

00

Figure

NDG12 Package Drawing -

page

APPROVED

DATE


06/21/16



# **Ordering Information**

Orderable Part Number	Package	Shipping Packaging	Temperature
5X2503-000NDGI	2.5 × 2.5 mm, 0.4mm pitch 12-DFN	Cut Tape	-40° to +85°C
5X2503-000NDGI8	2.5 × 2.5 mm, 0.4mm pitch 12-DFN	Reel	-40° to +85°C

# **Marking Diagram**



- 1. Line 1 is the truncated part number.
- 2. "000" denotes dash code.
- 3. "Y" is the last digit of the year the part was assembled.
- 4. "\*\*" denotes sequential lot number.

# **Revision History**

Revision Date	Description of Change
December 18, 2017	Corrected bit setting in Byte 24h, bit 2 from "1" to "0".
November 17, 2017	Updated register tables; Bytes 29, 30 and 32.
October 20, 2017	Initial release.

#### **IMPORTANT NOTICE AND DISCLAIMER**

RENESAS ELECTRONICS CORPORATION AND ITS SUBSIDIARIES ("RENESAS") PROVIDES TECHNICAL SPECIFICATIONS AND RELIABILITY DATA (INCLUDING DATASHEETS), DESIGN RESOURCES (INCLUDING REFERENCE DESIGNS), APPLICATION OR OTHER DESIGN ADVICE, WEB TOOLS, SAFETY INFORMATION, AND OTHER RESOURCES "AS IS" AND WITH ALL FAULTS, AND DISCLAIMS ALL WARRANTIES, EXPRESS OR IMPLIED, INCLUDING, WITHOUT LIMITATION, ANY IMPLIED WARRANTIES OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE, OR NON-INFRINGEMENT OF THIRD-PARTY INTELLECTUAL PROPERTY RIGHTS.

These resources are intended for developers who are designing with Renesas products. You are solely responsible for (1) selecting the appropriate products for your application, (2) designing, validating, and testing your application, and (3) ensuring your application meets applicable standards, and any other safety, security, or other requirements. These resources are subject to change without notice. Renesas grants you permission to use these resources only to develop an application that uses Renesas products. Other reproduction or use of these resources is strictly prohibited. No license is granted to any other Renesas intellectual property or to any third-party intellectual property. Renesas disclaims responsibility for, and you will fully indemnify Renesas and its representatives against, any claims, damages, costs, losses, or liabilities arising from your use of these resources. Renesas' products are provided only subject to Renesas' Terms and Conditions of Sale or other applicable terms agreed to in writing. No use of any Renesas resources expands or otherwise alters any applicable warranties or warranty disclaimers for these products.

(Disclaimer Rev.1.01)

#### **Corporate Headquarters**

TOYOSU FORESIA, 3-2-24 Toyosu, Koto-ku, Tokyo 135-0061, Japan www.renesas.com

#### **Trademarks**

Renesas and the Renesas logo are trademarks of Renesas Electronics Corporation. All trademarks and registered trademarks are the property of their respective owners.

#### **Contact Information**

For further information on a product, technology, the most up-to-date version of a document, or your nearest sales office, please visit <a href="https://www.renesas.com/contact-us/">www.renesas.com/contact-us/</a>.